


Site Code: MNO12	Location: AREA D	Grid Sq: 155/225	Context Type: MASONRY	Context Number: [4037]
1. Materials				
2. Size of materials (brick: BTL in mm)	1. hard hard peg tiles as a roof, hard mid orange, light orange and yellow beige bricks			
3. Finish of stones	2. 100mm x 60mm x 220mm			
4. Coursing / bond	3. moulded bricks - slightly frogged			
5. Form	4. stretchers on bed, forming a U-shaped profile			
6. Direction of face(s)	5. drain			
7. Surface treatment	6. N-S			
8. Bonding material (if brick: record height of 4 courses & 4 bed joints in m)	7. /			
9. Dimensions of masonry as found	8. soft light to mid yellow beige sand mortar in between the peg tiles on the drain roof and also at the bottom of the drain			
10. Other comments	9. 3.30m 3.30m (E-W); 0.40m (N-S);			
	10. /			
	Max Level: 10.74 m OD			
	Min Level: 10.60 m OD			

Stratigraphic Relationships:



Physical Relationships:

Abuts:	Abutted by:
Cut by:	

Interpretation:	internal	external <input checked="" type="checkbox"/>
E-W running drain in G. building (100 rineries). The drain has a peg tile roof that was planned as 4037a. The rest of the drain was planned as [4037b].		
Peg tile roof has 3 tiles on top of each other. The bottom of the drain is U-shaped with stretchers on bed. Peg tiles used for shimming, unlike [4046]; the fall of the drain drain is not exactly clear.		
The drain truncates and internal wall in Georgian building, running N-S.		
The southern edge of the wall was used as a side for the drain (see sketch overleaf).		
Context same as: [4046]		

Sample No(s): 2 tiles (broken) 2 bricks	Drawing No(s): 4037a (x1) (x) 4037b (x9)
Photo No(s):	Sketch/levels overleaf: <input checked="" type="checkbox"/> Transferred to plan: <input checked="" type="checkbox"/>

Compiled by: MK	Date: 24-06-2015	Checked by: c-7/10/15	Tick when entered in database: <input type="checkbox"/>
--------------------	---------------------	--------------------------	---

Context Number:
[4037]

Level No.s 1-9
TBM 11.40
B/S 0.46
IH 11.86

Level No.s 10-23
TBM 11.40
B/S 0.98
IH 12.38

Level No.s 24-25
TBM ~~11.40~~ 11.40
B/S 0.4066
IH ~~11.80~~ 12.06

Level No.s
TBM
B/S
IH

No.	F/S	R/L (m OD)	No.	F/S	R/L (m OD)	No.	F/S	R/L (m OD)	No.	F/S	R/L (m OD)
1	1.14	10.72	6	1.16	10.70	11	1.85	10.53	16	1.76	10.62
2	1.19	10.67	7	1.13	10.73	12	1.69	10.69	17	1.69	10.69
3	1.12	10.74	8	1.20	10.66	13	1.85	10.53	18	1.67	10.71
4	1.17	10.69	9	1.16	10.70	14	1.74	10.64	19	1.84	10.54
5	1.18	10.68	10	1.69	10.69	15	1.85	10.53	20	1.67	10.71
									21	1.66	10.72
									22	1.84	10.54
									23	1.66	10.72
									24	1.60	10.2046
									25	1.65	10.1541

